Department of Agriculture
HP Crop Diversification Promotion Project (Phase II), JICA-ODA
State H.Q. Agriculture Complex, Hamirpur Distt Hamirpur, H.P.-177001

Telefax: 91-1972-223059 **e-mail: pmucdp-hp@nic.in**

No. Agr.H.SPMU(G3)-IT/5/2022-Vol-III-Phase-II 2156-2163 Dated: 05-10-2026

Notice Inviting Tender for CCTV

The Project Director, HPCDP, JICA-ODA, Hamirpur invites sealed bids from leading manufacturers/distributors/dealers for the supply and installation in all respect (including testing) for Closed-circuit television (CCTV)/Video Surveillance System with minimum Three-year onsite warranty and the Comprehensive Annual Maintenance Contract (CMC) for the existing CCTV System at **HPCDP Administrative Building PMU, Agriculture Complex, Distt. Hamirpur, H.P. Pin Code- 177001** as per detail mentioned below.

S. No.	Description of Item	Qty.
A1.	Bullet IP camera (4MP), IR Range of 30 Mtrs, Day/Night (ICR) with 3-year onsite warranty	10 No.
A2.	Dome IP camera (4MP), IR Range of 30 Mtrs, Day/Night (ICR) with 3 year onsite warranty	
A3.	POE Switch 8+2, 4+2	As per requirement
A4.	Other Accessories including CAT 6 Cable, RJ 45 Connectors, Conduit Pipe, PVC Tape, Flexible Pipe etc.	As per site requirement
A5	Installation charges including- Labour, Installation, Programming, Testing and commissioning and training to users at the site to set the system up and operate the same	
B1.	Comprehensive Annual Maintenance Contract (CMC) for the existing CCTV surveillance system (comprising 15 cameras, DVR/NVR, and power supplies) for a period of one (5) year. Existing system installed in 2018.	

SCOPE OF WORK

The work shall comprise the supply, installation, integration, testing, commissioning and comprehensive maintenance of the CCTV Surveillance System at the HPCDP SPMU office premises.

1. **Existing CCTV Infrastructure:**
   The office has already installed 15 Nos. IP-based CCTV cameras, along with the associated CCTV surveillance infrastructure. The existing system shall be retained and integrated with the proposed additional CCTV infrastructure, wherever technically feasible.
2. **Additional CCTV Cameras:**
   The successful bidder shall supply, install, configure, test and commission 10 Nos. additional IP CCTV cameras at locations identified by the Department. The bidder shall ensure that the additional cameras are fully compatible with and integrated into the existing CCTV surveillance system.
3. **Integration of Complete System:**
   The existing 15 Nos. cameras and proposed 10 Nos. additional cameras, totalling 25 Nos. of CCTV cameras, shall function as an integrated surveillance system. Necessary

configuration, networking, software/VMS integration, storage, display and other associated works required for seamless operation shall be included in the scope.

4. **Testing and Commissioning:**
   The bidder shall undertake complete testing and commissioning of the integrated CCTV system, including camera connectivity, recording, live viewing, playback, storage, remote/local monitoring and other associated functionalities. The system shall be handed over to the Department in fully operational condition.

5. **Comprehensive Maintenance Contract (CMC):**
   The complete CCTV surveillance system comprising the existing 15 Nos. cameras and the additional 10 Nos. cameras (total 25 Nos.) shall be covered under Comprehensive Maintenance Contract (CMC) for a period of 5 (five) years from the date of successful commissioning/handing over of the additional system.

6. **Coverage under CMC:**
   The CMC shall cover preventive and corrective maintenance of the complete CCTV system, including cameras, NVR/VMS, storage devices, network components, power-related accessories, cables/connectors and other associated CCTV equipment installed under the system. The bidder shall attend to faults, undertake necessary repairs/replacement of defective components and ensure uninterrupted functioning of the surveillance system throughout the CMC period, as per the terms and conditions of the NIQ.

7. **Overall Responsibility:**
   The bidder shall be responsible for ensuring the end-to-end operational readiness and maintenance of the complete 25-camera CCTV surveillance system during the contract/CMC period, irrespective of whether the equipment is existing or newly supplied, subject to the terms and conditions specified in the NIQ.

8. **Site visit:**
   The bidders/tenderer are requested to visit the site before submitting the bid. The CCTV Cameras are to be installed in Inside and outside of the Administrative Building of HPCDP JICA-ODA Hamirpur. Hence the bidders can inspect the site before quoting their rates.

Terms and conditions

1. Tender must be enclosed in a properly sealed envelope addressed to The Project Director, HPCDP (Phase-II), JICA-ODA Hamirpur. or before 21st Oct. 2026 by 11 A.M. and the same shall be opened on the same date at 11:15 A.M. by the committee in the presence of the bidders/or their representatives.
2. The tender document should be duly signed by the tenderer.
3. The bid document contains financial bid separately for Part A and B as per ***Annexure-I***. and L1 will be worked out on the basis of total of A+B
4. Earnest Money for Rs. 5,000/- (Rupees Five thousand only) and tender cost @ Rs. 100/- in the shape of Demand Draft payable to The Project Director, HPCDP (Phase-II), JICA-ODA Hamirpur.
5. All taxes, GST or any charges should be indicated separately otherwise rates will be deemed to be inclusive of taxes and no future increase will be allowed.
6. Only CP Plus brand product with ISI certification is required as the existing system is of CP Plus brand.
7. The supply of Closed-circuit television (CCTV)/Video Surveillance System and its installation have to be completed within 10 days after the issue of supply order.

8. The tenders who do not fulfill the above-mentioned conditions their tender will be straight way rejected.
9. The Project Director reserves the right to accept or reject any or all the bids without assigning any reason.
10. The rates quoted by the bidders should be less than the prevailing rates available on the Government e-Marketplace (GeM) Portal.
11. The New Closed-circuit television (CCTV)/Video Surveillance System and all other accessories should be genuine/branded & having minimum two-year onsite warranty and after sale service.
12. Performance security will be obtained from the successful tenderer on the award of contract @ Rs. 5000/- (Rs. Five Thousand only), in the shape of FDR duly pledged in favour of Project Director, HPCDP JICA Hamirpur. The performance security shall remain during the period of CMC i.e. 3 years.
13. The payment of new CCTV including accessories shall be released immediately after successful installation and testing.
14. The payment of CMC shall be paid half-yearly.
15. The rates for all types of accessories not included in the bid may be quoted separately along with brand name.
16. The rates quoted shall remain valid up to 60 days from the date of receipt of bid.
17. All disputes will be subject to Hamirpur courts only.

Digitally signed by
DR SUNIL CHAUHAN
Date: 01-10-2026
15:22:26

Project Director,
HPCDP JICA-ODA Hamirpur,
Distt. Hamirpur (H.P.).

Endst. No. Agr.H.SPMU(G3)-IT/5/2022-Vol-III-Phase-II 2156-2163 dated 05-10-2026
Copy to:

1. Notice Board HPCDP JICA-ODA Hamirpur.
2. HPCDP Website
3. M/S IT Solutions, Jhaniari, Hamirpur, Himachal Pradesh (HP-02) 177001.
4. M/S SN Services Shop No. 3 Vill. Lalhari By Pass Road Hamirpur Near Sai Motor Teh & Distt Hamirpur, (H.P), 177001.
5. M/S Microtech Computers, Shop No. 4, Prabh Kirti Complex, Near K.C.C. Bank Dev Pal Chowk, Hamirpur (H.P.).
6. M/S Microcom Computers Below State Bank of India Gandhi Chowk, Hamirpur (H.P.).
7. A.S Infotech Soharu Complex Dayanand Chowk Opp. Sub Post office Hamirpur.
8. M/S Shivam Technologies, Shop NO. 120, Satya Shopping Complex, New Road, Hamirpur (H.P.).

Project Director,
HPCDP JICA-ODA Hamirpur,
Distt. Hamirpur (H.P.).

Annexure -I

Sr. No.	Description of Item / Service	Qty		Unit Rate (₹)	Applicable GST (₹)	Total Amount inclusive of all Taxes (₹)
A	**New Supply & Installation**					
1	4MP IP Dome/ Bullet Camera (4MP), IR Range of 30 Mtrs, Day/Night(ICR)	10 Nos	Bullet			
			Dome			
2	POE Switch 8+2 & 4+2					
3	Cabling/Wiring charges per meter (approx. estimate) along with accessories					
4	Installation charges					
B	**Comprehensive Annual Maintenance**					
5	CMC of existing CCTV system (including NVR, HDD, existing cameras, and power supplies) for 5 Years on yearly basis	1 Job				
	Grand Total (A + B)					